

Schedule of Quantities - Tile work for Classroom RN-4 and RS-1 in College campus at St. Stephen's College, Delhi.

S. No.	Description	Qty.	Unit	Rate	Amount
1.01	Providing and laying selected rectified / fully vitrified and joint less floor tiles of size 300x300 mm to 600x600 mm of 1st quality of approved make laid on epoxy grout (Laticrete make) including grouting the joints with white cement and matching pigments etc. complete. Make: Kajaria, Somany. (Sample to be got approved prior to placing order). (Base rate Rs.45/- Sq.ft)	35	Sqm		
1.02	Providing and fixing 1st quality joint less ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacture's) of approved make in all colours, shades of 200x300 mm / 300x600 mm size as approved by the Architect, in skirting and dados, laid on epoxy grout (Laticrete make) including grouting the joints with white cement and matching pigments etc. complete. Make: Kajaria, Somany. (Sample to be got approved prior to placing order).	4	Sqm		
	Total				