

<b>Schedule of Quantities - Painting work for College Gym at St. Stephen's College, Delhi.</b>					
<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
<b>Note:</b>	Demolition shall not be done by mechanical means.				
1.01	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	11	Sqm		
1.02	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	55	Sqm		
1.03	Applying one coat of water thinnable cement primer of approved brand: Water thinnable cement primer.	37	Sqm		
1.04	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	87	Sqm		
1.05	Finishing walls with Acrylic smooth exterior paint of required shade: Old work (One or more coat applied @ 0.90 ltr/10 sqm).	80	Sqm		
1.06	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: (Two or more coats on new work.)	51	Sqm		
1.07	Providing and finishing with melamine polishing (two or more coats on new works including a coat of wood filler. <b>(Sample to be got approved).</b>	106	Nos		
	<b>Total</b>				